

15-135-20490-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling and Petroleum Resources

Complete Address Box 18407 Wichita, Kansas

Lease Name Solze Well No. 1

Location SW SW SE Sec. 28 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4470'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well (as hereafter indicated)

Plugging Contractor Red Tiger Drlg

Address Wichita, Kansas License No.

Operation Completed: Hour 2:30 P Day 17 Month 10 Year 1971

The above well was plugged as follows:

RTD 4470' 8 5/8 csg set at 289' cwc Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10-18-71

INV. NO. 4492-W