

15-135-2138-0000



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 25 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas. 67217

Operator's Full Name Pickwell Drilling Co.

Complete Address 705 4th Natl. Bk. Bldg., Wichita, Kansas

Lease Name Popp "B" Well No. 1

Location C NE NE Sec. 25 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4407'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 2:40 A Day 24 Month 4 Year 1975

The above well was plugged as follows:

RTD 4407' 8 5/8 csg set 210' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 715' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Red Z. Manship  
Well Plugging Supervisor

INVOICED

DATE 4/29/75

INV. NO. 1250-W