

15-135-20722-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling & Petroleum Resources

Complete Address Box 18407 Wichita, Kansas

Lease Name Stoppel Well No. 1

Location NW NE Sec. 27 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4330'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XXX

Other well as hereafter indicated

Plugging Contractor Strata Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 11 A Day 13 Month 1 Year 1973

The above well was plugged as follows:

RTD 44330' 8 5/8 csg set at 354' cwc 195 sk. Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Muesy
Well Plugging Supervisor

INVOICED

DATE 1-15-73

INV. NO. 6854-W