

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 09 1977
CONSERVATION DIVISION
Wichita, Kansas well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,350 - 000

Operator's Full Name Vincent Oil Corp.

Complete Address 901 Union Center Bldg., Wichita, Kansas

Lease Name Gabel Well No. 1

Location 150'S of C SE NW Sec. 22 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4326'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Slawson Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11:45 A Day 7 Month 8 Year 1977

The above well was plugged as follows:

RTD 4326' 8 5/8 csg set 312' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid-
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

8-11-77

NO. NO.

5633-W