

15-135-20378-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED
OCT 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Co, Inc. & Dunne -Gardner Petroleum, Inc.

Complete Address 905 Century Plaza Wichita, Kansas

Lease Name Gabel Well No. 1

Location C SE SW Sec. 22 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4355

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dunne -Gardner

Address Wichita, Kansas License No.

Operation Completed: Hour 5.30P Day 21 Month 10 Year 1970

The above well was plugged as follows:

RTD 4355' 8 5/8 csg set at 330' cwc 250 sk. Cmt. Mat. 100 sk reg poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: L. F. Massey
Well Plugging Supervisor

INVOICED

DATE 10/23/70
INV. NO. 2941-W