

15-135-20086-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1967
12-06-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawsom

Complete Address: 408 One Twenty Bldg., Wichita, Ks.

Lease Name Schwartz "D" Well No. 1

Location C NW NW Sec. 8 Twp. 18 Rge. 22 (E) (W) X

County Ness Total Depth 4247'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 2:30 A Day 5 Month 12 Year 1967

The Above well was plugged as follows:

RTD 4247' 8 5/8 csg set at 301' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 270' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. F. Massey
Well Plugging Supervisor

INVOICED

DATE 12/6/67
INV. NO. 6853-W