

15-B5-20127-00-00

Form CP-3
Rev. 6-4-68

KANSAS

JL
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 3 1969
CONSERVATION DIVISION
Wichita, Kansas
12-03-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 Fourth Nat'l Bldg., Wichita, Ks.

Lease Name Wegele "A" Well No. 1

Location G NW SW Sec. 22 Twp. 18 Rge. (E) (W) 22

County Ness Total Depth 4329'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 12:30P Day 1 Month 12 Year 1969

The above well was plugged as follows:

Total Depth 4329' 8 5/8 csg set at 255' cwc

5 1/2 csg set at 4319' cw 80 sk cmt.

5 1/2 csg Perf. (4239-4244)

Filled 5 1/2 csg W/sd (4200-4329) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 2339' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 16 sk gel W/3 sk hulls, 80 sk 50-50 poz 6%,

4 sk gel, plug and 20 sk 50-50 poz. 6%.

Cmt. (0-80) gel (80-240) Cmt (240-560) Gel & Hulls (560-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bio T. Messing
Well Plugging Supervisor

DATE 12/3/69
INV. NO. 969-W