

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26288-00-00
Spot: NESESWNE Sec/Twnshp/Rge: 18-12S-18W
1995 feet from N Section Line, 1575 feet from E Section Line
Lease Name: STACKHOUSE Well #: 1
County: ELLIS Total Vertical Depth: 3845 feet

Operator License No.: 4787
Op Name: TDI, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/01/2012 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: DERBY Company: SOUTHWIND DRILLING, INC. Phone: (785) 259-1356

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 06/01/2012 8:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @1550 w/25 sx
2nd plug @875 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

RECEIVED
JUN 07 2012
KCC WICHITA

Remarks: QUALITY

Plugged through: DP

District: 04

Signed

C. A. Morris
6/15/12 (TECHNICIAN)

JUN 04 2012