

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21441-00-00  
Spot: SENWNWNE Sec/Twnshp/Rge: 4-33S-19W  
447 feet from N Section Line, 2295 feet from E Section Line  
Lease Name: DEWAYNE HERD Well #: 3-4  
County: COMANCHE Total Vertical Depth: 5976 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5065		WITH 2 SX CMT
CIBP		5800		
COND	20	43		
PROD	4.5	5961	3525	WITH 225 SX CMT
SURF	8.625	652		WITH 325 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/30/2012 10:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: DAVID HAYES Company: OIL PRODUCERS Phone: (620) 546-4456

Proposed Plugging Method: SET CIBP @ 5065' WITH 2 SX CMT. PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/30/2012 11:25 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5065' WITH 2 SX CMT. 1ST PLUG AT 940' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 677' WITH 50 SX CMT. 3RD PLUG AT 58' WITH 20 SX CMT. CMT CIRCULATED BUT FELL APPROXIMATELY 70'. 6/1/12: TOPPED OFF WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5916	5926		VIOLA
5873	5926		VIOLA
5220	5246		MISS
5150	5210		MISS
5130	5133		MISS
5116	5246		MISS

RECEIVED  
JUN 08 2012  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

JUN 06 2012

KCC DODGE CITY

Signed

Eric MacLaren  
6/15/12

(TECHNICIAN)

B9/12