

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20968-00-00  
Spot: N2NESENE Sec/Twnshp/Rge: 4-33S-19W  
1602 feet from N Section Line, 327 feet from E Section Line  
Lease Name: HERD Well #: 2B-4  
County: COMANCHE Total Vertical Depth: 5340 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4936		WITH 2 SX CMT
COND	20	150		
PROD	4.5	5342	3117	WITH 235 SX CMT
SURF	8.625	643		WITH 495 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/01/2012 10:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: DAVID HAYES Company: OIL PRODUCERS Phone: (620) 546-4456

Proposed Plugging Method: SET CIBP @ 4930' WITH 2 SX CMT. PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. PLUG AT 670' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/01/2012 11:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4936' WITH 2 SX CMT. 1ST PLUG AT 956' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 673' WITH 50 SX CMT. 3RD PLUG AT 58' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5195	5252		
5034	5038		
4986	5014		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED  
JUN 08 2012  
KCC WICHITA

District: 01

Signed: Eric McLaren (TECHNICIAN)  
6/15/12

RECEIVED  
JUN 06 2012  
KCC DODGE CITY

raw