

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21313-00-00
Spot: SENEWSWE Sec/Twnshp/Rge: 17-32S-2E
981 feet from S Section Line, 1637 feet from E Section Line
Lease Name: EVANS Well #: 5
County: SUMNER Total Vertical Depth: 3707 feet

Operator License No.: 7186
Op Name: DOCKING DEVELOPMENT COMPANY,
Address: PO BOX 928
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3704		300 SX
RBP		3050		
SURF	8.625	253		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2012 10:15 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: LARRY BARTELSON Company: DOCKING DEVELOPMENT Phone: (620) 455-3444

Proposed Plugging Method: CIBP 50' ABOVE TO PERFS. PERF @ 300' & CIRC CEMENT.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 05/23/2012 10:15 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 2820' & CAPPED WITH 28 SKS OF CMT. PERFORATION HOLES WERE SHOT AT 300'. TUBING WAS RUN TO 300' & CEMENT WAS CIRCULATED UP THE 4 1/2. BACKSIDE OF 4 1/2 PRESSURED UP TO 500#.

Perfs:

Top	Bot	Thru	Comments
3704	3707	CSG	
2980	2984	CSG	
2874	2878	CSG	

KCC WICHITA
JUN 08 2012
RECEIVED

Remarks: COPELAND CEMENT TICKET #37921. 95 SX -- PLUG DUE TO COMPLAINT.

Plugged through: TBG

District: 02

Signed 
6/15/12 (TECHNICIAN)

124