

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21976-00-00  
Spot: W2SESESE Sec/Twnshp/Rge: 10-16S-16W  
330 feet from S Section Line, 410 feet from E Section Line  
Lease Name: DENNIS BOXBERGER Well #: 1-10  
County: RUSH Total Vertical Depth: 3595 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| SURF   | 8.625 | 1010       |             | WITH 400 SX CMT |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/04/2012 9:45 AM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Revd. from: RANDY MARTIN Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 3495' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 50 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE  
Date/Time Plugging Completed: 06/04/2012 11:45 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 3495' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 50 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
JUN 06 2012  
KCC DODGE CITY

RECEIVED  
JUN 08 2012  
KCC WICHITA

RAY