

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22498-00-00
Spot: NESENE Sec/Twnshp/Rge: 8-35S-2E
1650 feet from N Section Line, 330 feet from E Section Line
Lease Name: MESSENGER Well #: 1
County: SUMNER Total Vertical Depth: 3691 feet

Operator License No.: 3833
Op Name: SHAIDA, JOHN H.
Address: 4126 N SWEET BAY CIR
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2300		
CIBP	5.5	3000		
PROD	5.5	3628	1925	
SURF	8.625	261		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/11/2012 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: SAND TO 3400' & 5 SKS, REC PIPE, CIRC CEMENT 310'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 05/11/2012 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SAND TO 3390 & 5 SKS, CIBP @ 3000' & 2 SKS, CIBP @ 2300' & 2 SKS. REC 1925' OF 5 1/2. PULLED CASING TO 310' & CIRC'D CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3444	3464	CSG	MISSISSIPPI
3017	3023	CSG	LANSING
2354	2356	CSG	STALNAKER

RECEIVED
JUN 08, 2012
KCC WICHITA

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

VJK