

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21146-00-00  
Spot: SENESE Sec/Twnshp/Rge: 7-29S-6W  
3630 feet from N Section Line, 330 feet from E Section Line  
Lease Name: W KAUFMAN Well #: 2  
County: KINGMAN Total Vertical Depth: 4546 feet

Operator License No.: 5348  
Op Name: CAMPBELL, ROBERT E.  
Address: 260 N ROCK RD STE 110  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4546	2430	350 SXS CMT
SURF	8.625	235		225 SXS CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/16/2012 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: SAND BACK TO 3969 & 4 SXS, 35 SX 1000', 35 SX 600, CIRC 300-0'.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/30/2012 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3969' AND CAPPED WITH 4 SKS CMT. THE 4 1/2 WAS RECOVERED FROM 2430' AND PULLED TO 1000', WHERE 35 SXS OF CMT WAS SPOTTED. PULLED CASING TO 600' & SPOTTED 35 SXS CMT. PULLED CASING TO 300' AND CIRC CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4549	4550	OH	
4130	4142	CSG	


RECEIVED  
JUN 08 2012  
KCC WICHITA

Remarks: QUALITY WELL SERVICE 60/40 4% GEL. DENIED TA

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

  
6/14/12 (TECHNICIAN)