

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-10077-00-00
Spot: NENWNW Sec/Twnshp/Rge: 18-31S-8W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: DARNES Well #: A1
County: HARPER Total Vertical Depth: 4459 feet

Operator License No.: 3288
Op Name: JODY OIL & GAS CORPORATION
Address: PO BOX 422
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4439	1435	75 SX
SURF	8.625	186		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2012 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: SAND TO 4380 & 5 SKS. REC PIPE. 35 SX 1400', 35 SX 950', CIRC 245'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 05/17/2012 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE OPEN HOLE WAS FILLED BACK TO 4312' & CAPPED WITH 5 SKS CEMENT.
THE CASING WAS RECOVERED FROM 1435' & PULLED TO 1370' WHERE 35 SX OF
CEMENT WAS SPOTTED. PULLED CASING TO 950' & SPOTTED 35 SX CEMENT.
PULLED CASING TO 245' & CIRC'D CEMENT TO SURFACE WITH 130 SX.

Perfs:

Top	Bot	Thru	Comments
4439	4459	OH	

RECEIVED
JUN 08 2012
KCC WICHITA

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____


6/15/12 (TECHNICIAN)

JK