

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21087-00-00
Spot: E2NWNESW Sec/Twnshp/Rge: 11-32S-9W
2593 feet from S Section Line, 3679 feet from E Section Line
Lease Name: NEWBERRY Well #: SWD
County: HARPER Total Vertical Depth: 4378 feet

Operator License No.: 5039
Op Name: AGV CORP.
Address: PO BOX 377
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4167		
PROD	5.5	3863	2250	100 SX
SURF	8.625	251		200 SX

Well Type: SWD UIC Docket No: D27514.0 Date/Time to Plug: 05/18/2012 12:00 AM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: DAVE MILLER Company: AGV Phone:

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS, CAP WITH 2 SKS CEMENT. REC PIPE 35 SX 1500', 35 SX 950', CIRC CEMENT 300'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 05/18/2012 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3850' AND CAPPED WITH 2 SKS OF CEMENT. THE PIPE WAS RECOVERED FROM 2250' AND PULLED TO 1540' WHERE 35 SKS OF CEMENT WAS SPOTTED & PULLED CASING TO 952' WHERE 35 SKS OF CEMENT WAS SPOTTED. PULLED CASING TO 322' WHERE CEMENT WAS CIRC'D TO SURFACE. PULLED CASING FROM HOLE AND TOPPED OFF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4360	4378	CSG	
3898	4067	CSG	
3893	4062	CSG	

RECEIVED
JUN 08 2012
KCC WICHITA

Remarks: ALLIED CEMENTING

Plugged through: CSG

District: 02

Signed


(TECHNICIAN)

✓ cc of 2/3 to WIC 6/14/12
6/14/12