

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-10165-00-01 J
Spot: SENWSESW Sec/Twnshp/Rge: 18-22S-22W
672 feet from S Section Line, 3306 feet from E Section Line
Lease Name: OPPY Well #: 2
County: HODGEMAN Total Vertical Depth: 4599 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4367		
PROD	5.5	4599	0	WITH 175 SX CMT
SURF	10.75	306		WITH 306 SX CMT

Well Type: SWD UIC Docket No: D27246.0 Date/Time to Plug: 05/31/2012 9:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM Phone: (620) 792-6702

Proposed Plugging Method: PUMP TBG VOLUME OF CMT THEN ADD 25# HULLS TO CMT & PRESSURE TO 500# WITH CMT. PRESSURED TEST 5 1/2" X 2 7/8" ANNULUS TO 500#. PRESSURED TEST 10 3/4" X 5 1/2" ANNULUS TO 500#.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/31/2012 11:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TIED ONTO TBG & PUMPED 140 SX CMT, WITH 200# HULLS ON THE LAST HALF. PRESSURED REACHED 500# SEVERAL TIMES, ONLY TO BLEED OFF TO ABOUT 200#. TIED ONTO THE 5 1/2" X 2 7/8" ANNULUS & PUMPED 75 SX CMT WITH 100# HULLS ON THE LAST HALF. PRESSURE REACHED 900# SEVERAL TIMES, ONLY TO BLEED OFF TO ABOUT 200#. TIED ONTO THE 10 3/4" X 5 1/2" ANNULUS & PUMPED 15 SX CMT. PRESSURED TO 400#.

Perfs:

Top	Bot	Thru	Comments
4521	4524		
3456	4547		
2500	3200		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

RECEIVED
JUN 08 2012
KCC WICHITA

District: 01

Signed Eric MacLaren
6/15/12 (TECHNICIAN)

RECEIVED
JUN 06 2012
KCC DODGE CITY

RAW