

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21821-00-00
Spot: SWNWSENE Sec/Twnshp/Rge: 32-16S-30W
1758 feet from N Section Line, 1095 feet from E Section Line
Lease Name: STEWART 32 A Well #: 1
County: LANE Total Vertical Depth: 4636 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		2243		
PROD	4.5	4632	0	WITH 200 SX CMT
SURF	8.625	307		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/30/2012 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: PUMP DOWN CASING WITH 30 SX CMT & 150# HULLS. PUMP GEL SPACER TO 2282'. PUMP CMT UNTIL IF CIRCULATES TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/30/2012 10:05 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

PUMPED DOWN 4 1/2" W/30 SX CMT W/150# COTTON SEED HULLS MIXED IN - 30 SX GEL - 125 SX CMT. INITIAL SHUT IN PRESSURE = 750 PSIG. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 300 PSIG WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4534	4536		
4524	4536		
4490	4492		
4476	4480		
4442	4446		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Kenny Sullivan
6/15/12

(TECHNICIAN)

RECEIVED

JUN 07 2012

KCC DODGE CITY

RECEIVED
JUN 13 2012
KCC WICHITA