

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-30382-00-02 7
Spot: N2NENW Sec/Twnshp/Rge: 30-33S-11W
323 feet from N Section Line, 2220 feet from W Section Line
Lease Name: FITZGERALD - A Well #: 1
County: BARBER Total Vertical Depth: 4644 feet

Operator License No.: 31938
Op Name: INDIAN OIL CO., INC.
Address: PO BOX 209 2507 SE US 160 HWY
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4524		
CIBP		4561		
PROD	4.5	4642	0	WITH 110 SX CMT
SURF	8.625	305		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2012 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: RUN TBG TO 4500' & PUMP 15 SX GEL & 50 SX CMT. PERFORATE 4 1/2" CASING @ 600'. PUMP CMT DOWN 4 1/2" UNTIL CMT CIRCULATES TO SURFACE UP 8 5/8" X 4 1/5" ANNULUS.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2012 2:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

****COULDN'T WORK 2 3/8" TBG PAST 3900' DUE TO COLLAPSED CASING.** RAN TBG TO 3900' & PUMPED 15 SX GEL - 50 SX CLASS A CMT W/3% CC. GOOD CIRCULATION. TAGGED CMT TOP @ 3180'. PRESSURE TEST 4 1/2" CASING TO 500 PSIG. PERFORATED 4 1/2" @ 600'. PUMPED 235 SX CMT DOWN 4 1/2" CIRCULATING CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS.**

Perfs:

Top	Bot	Thru	Comments
4555	4559		
4547	4553		
4503	4511		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey (TECHNICIAN)
6/15/12

RECEIVED

JUN 07 2012

KCC DODGE CITY

RECEIVED
JUN 13 2012
KCC WICHITA