

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20179-00-02

Spot: SENW

Sec/Twnshp/Rge: 6-33S-40W

3343 feet from S Section Line, 3216 feet from E Section Line

Lease Name: LOW G

Well #: 1 (SWD)

County: MORTON

Total Vertical Depth: 5450 feet

Operator License No.: 32446

Op Name: MERIT ENERGY COMPANY, LLC

Address: 13727 NOEL RD STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3350		WITH 5 SX CMT
PROD	4.5	5449	1590	WITH 125 SX CMT
SURF	8.625	1587		WITH 800 SX CMT

Well Type: SWD

UIC Docket No: D18269.0

Date/Time to Plug: 05/16/2012 9:00 AM

Plug Co. License No.: 33338

Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: RONNIE ORR

Company: ORR ENTERPRISES, INC.

Phone: (580) 251-9618

Proposed Plugging Method: PLUG AT 3400' WITH 50 SX CMT. PLUG AT 1600' WITH 80 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: PARTIAL

Date/Time Plugging Completed: 05/16/2012 3:30 PM

KCC Agent: JACK MACLASKEY

Actual Plugging Report:

Perfs:

SET CIBP @ 3350'. PUMP 50 BBL MUD & 5 SX CMT. 1ST PLUG AT 1600' WITH 80 SX CMT. 2ND PLUG AT 500' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Top	Bot	Thru	Comments
5364	5400		MORROW UPPER

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey  
(TECHNICIAN)  
6/15/12

RECEIVED

MAY 30 2012

KCC DODGE CITY

Form CP-2/3

RECEIVED  
JUN 13 2012  
KCC WICHITA