

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20542-00-00  
Spot: NESWNESW Sec/Twnshp/Rge: 10-29S-14W  
1909 feet from S Section Line, 3371 feet from E Section Line  
Lease Name: MOSS Well #: 2  
County: PRATT Total Vertical Depth: 2200 feet

Operator License No.: 31938  
Op Name: INDIAN OIL CO., INC.  
Address: PO BOX 209 2507 SE US 160 HWY  
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2105		WITH 2 SX CMT
CIBP		2212		
PROD	4.5	2209	0	
SURF	8.625	360		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2012 9:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 2100' & PUT 2 SX CMT ON TOP OF CIBP. PLUG AT 880' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/11/2012 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2105' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PRESSURE TEST CASING TO 300#. HELD. PERFORATE 4 1/2" @ 880'. PUMP DOWN 4 1/2" CASING WITH 300 SX CMT. EXCELLENT RETURNS TO NO RETURNS. SHUT DOWN. 6/11/12: TAG CMT IN 4 1/2" @ 3'. FOUND FLUID IN 4 1/2" X 8 5/8" ANNULUS AT 7' FROM SURFACE. CUT BRADEN HEAD OFF TO GET SLIPS OUT. RUN SUCKER RODS DOWN ANNULUS & TAG TOC @ 165'. RUN 1" TBG IN TO 140'. PUMPED DOWN 1" TBG WITH 33 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2165	2171		
2155	2160		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED

Plugged through: CSG

District: 01

Signed

*Stephen J. Pfeifer*  
6/15/12  
(TECHNICIAN)

RECEIVED  
JUN 14 2012  
KCC WICHITA

RECEIVED  
JUN 12 2012

JUN 12 2012  
KCC DODGE CITY  
KCC DODGE CITY

AMJ