

15-135-22064-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Ness SEC. 9 TWP. 17 RGE. 24W
 Location as in quarters or footage from lines:
C SW NW

Lease Owner Walters Drilling Company, Inc.
 Lease Name Phelps 'C' Well No. 1
 Office Address 420 Hardage Center, 100 S. Main, Wichita 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 7/15/81
 Application for plugging filed 7/15/81
 Plugging commenced 7/15/81
 Plugging completed 7/15/81 1:30 a.m.
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom _____ T.D. 4460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	368	8-5/8"	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

1st plug @ 900' with 65 sx 50/50 Poz, 4% gel, 3% CC
 2nd plug @ 390' with 30 sacks 50/50 Poz, 4% gel, 3% CC
 Bridge @ 40' with 10 sacks, 50/50 Poz, 4% gel, 3% CC
 5 sacks in rathole
 Job complete @ 1:30 a.m. 6/15/81

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


James C. Remsberg, Slawson Drilling (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
200 Douglas Building, Wichita 67202
 (Address)

SUBSCRIBED AND SWORN TO before me this 24 day of July, 1981

My Commission Expires: January 17, 1985

Mary Lou Taylor
 Mary Lou Taylor
 NOTARY PUBLIC
 STATE CORPORATION COMMISSION



JUL 28 1981
 07-28-1981
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLERS LOG

JUL 28 1981

STATE CORPORATION COMMISSION

1891-87-10

RECEIVED

OPERATOR: Walters Drilling Company, Inc.
420 Hardage Center, 100 South Main
Wichita, Kansas 67202

WELL NAME: Phelps 'C' #1
C SW NW Sec. 9-17S-24W
Ness County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 7/8/81

COMPLETED: 7/15/81

RTD: 4460'

SURFACE CASING: 8-5/8" set at 368' with 275 sx

0' to 375' Surface Hole
375' to 415' Shale
415' to 1713' Shale & Shells
1713' to 1755' Anhydrite
1755' to 2060' Shale & Shells
2060' to 2800' Shale
2800' to 3390' Shale & Lime
3390' to 3642' Lime & Shale
3642' to 3900' Shale & Lime
3900' to 4114' Lime & Shale
4114' to 4251' Shale & Lime
4251' to 4460' Lime
RTD 4460'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the Phelps 'C' #1 log for Walters Drilling Company, Inc.

James C. Remsberg
James C. Remsberg

Subscribed and sworn to me this
24th day of July, 1981

Mary Lou Taylor
Mary Lou Taylor, Notary

My commission expires January 17, 1985

