


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 9 Twp. 17S Rge. 24W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE SW
Lease Owner Palomino Petroleum
Lease Name Rufenacht #1 Well No.
Office Address P.O. Box 18610 Wichita, Kansas 67218
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8-12-81 19
Plugging completed 8-17-81 19
Reason for abandonment of well or producing formation

Depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4435'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	368'	none
				4-1/2"	4433'	1989'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in on location, ran sand to 4200' and set 4 sacks cement. Short cased worked pipe @3500', 3180', 3008', 2865', 2745', 2623', 2495', 2370', 2247', 2124' & 2080'. Pulled 63 joints. Plugged well with 25 sacks gel, 5 sacks hulls, 8 5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1981
08-27-1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
R. Darrell Kelso
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 81

My commission expires



Irene Hoover
Notary Public.

15-135-21951-00-00

DRILLERS LOG

#1 Rufenacht

CASING RECORD:
9 jts. used 8-5/8"
surface casing

COMPANY: Vincent Oil Corporation
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C SE SW
Section 9-17S-24W
Ness County, Kansas

COMMENCED: February 3, 1981

TOTAL ROTARY
DEPTH:

COMPLETED: February 12, 1981

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand, shale	0	190	Ran 363' used 8-5/8" surface casing; set and cemented @ 368' with 210 sks. common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 7:00 p.m. February 3, 1981.
Shale	190	373	
Shale, sand, shale	373	1680	
Anhydrite	1680	1713	
Shale	1713	2050	
Lime and shale	2050	4378	Ran 5 drill stem tests. Ran one electric log.
Lime	4378	4415	
Lime and shale	4415	4435	
			Ran 132 jts. 4 1/2" casing; set at 4433' with 175 sacks 60-40 pozmix, 10 bbl. salt flush. Plug down at 11:55 a.m., February 12, 1981.

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1981
06-26-1981
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp

Sworn to and subscribed before me this 18th day of February, 1981.

My appointment expires 3-28-84.

Loneita Barry
Loneita Barry, Notary Public

