

15-135-21084-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Ness County, Sec. 9, Twp. 17S Rge. (E) 24 (W)  
Location as "NE/CNW/SW" or footage from lines C/SW SW

Lease Owner Okmar Oil Company  
Lease Name Tilley Well No. 1  
Office Address 970 Fourth Financial Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 23 19 75  
Application for plugging filed September 23 19 75  
Application for plugging approved September 23 19 75  
Plugging commenced September 23 19 75  
Plugging completed September 23 19 75  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4432 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	327'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole plugged as follows: Plugged at 720' with 70 sacks of 50-50 pozmix sand 6% gel; plugged at 300' with 20 sacks pozmix and 6% gel; plugged at 40' with 10 sacks of pozmix and 6% gel. Plug down at 10:00 P. M. September 23, 1975.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 1 1975

CONSERVATION DIVISION  
Wichita, Kansas

10-01-1975

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company  
Address P. O. Box 355, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF BARTON, ss.

Kenneth J. Link (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link  
Kenneth J. Link, President  
Box 355, Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 29th day of September, 1975.  
Elaine H. Taylor  
Elaine H. Taylor Notary Public.

My commission expires December 14, 1977



DRILLERS LOG

15-135-21084-00-00

#1 Tilley

CASING RECORD:  
321' of used 8-5/8"  
surface casing.

COMPANY: Okmar Oil Company  
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C/SW SW  
Section 9-17S-24W  
Ness County, Kansas

TOTAL DEPTH:  
4432'

COMMENCED: September 13, 1975  
COMPLETED: September 23, 1975

D. & A.

FORMATION	FROM	TO	REMARKS
Surface Soil	0	340	Ran 321' of used 8-5/8" surface casing; set and cemented at 327' with 185 sacks of common cement, 2% gel and 3% C. C. Plug down at 5:00 P. M. September 14, 1975.
Shale	340	530	
Shale & Sand	530	1114	
Shale & Sand - Anhydrite	1114	1765	
Shale & Red Bed	1765	2250	
Lime & Shale	2250	4231	
Lime	4231	4255	
Lime & Shale	4255	4414	
Lime	4414	4432	

ROTARY TOTAL DEPTH: 4432'

Ran Drill Stem Tests.

No electric log was run.

D. & A.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 1 1975  
10-01-1975  
CONSERVATION DIVISION  
Wichita, Kansas

Hole plugged as follows: Plugged at 700' with 70 sacks of 50-50 pozmix and 6% gel; plugged at 300' with 20 sacks of pozmix and 6% gel; plugged at 40' with 10 sacks of pozmix and 6% gel. Plug down at 10:00 P. M. September 23, 1975.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link, President

Subscribed and sworn to before me this 29th day of September, 1975.

My Commission Expires:  
December 14, 1977

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

