


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 36 Twp. 17S Rge. 24 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C. SW $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner MCAAM Oil Company, Inc.
Lease Name Yost Well No. 1
Office Address 250 No. Rock Rd, Suite 150, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above
Section Plot

Date Well completed September 26 1981
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced September 26 1981
Plugging completed September 26 1981
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation. Depth to top Bottom Total Depth of Well 4466'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	330	8 5/8"	321	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with 50/50 pozmix, 4% gel, 3% CaCl, as follows:

- 70 sacks @ 960'
- 40 sacks @ 300'
- 10 sacks and hulls @ 40'
- 5 sacks in mousehole
- 5 sacks in rathole

RECEIVED
STATE CORPORATION COMMISSION

OCT 5 1981
10-05-1981
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Mallard Drilling Co., Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
John Jay Darrah, Jr., Agent (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John Jay Darrah
405 Century Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of September, 19 81.

Dianne R. Fowler, Notary Public.

My commission expires August 25, 1981



15-135-22038-00-00

DRILLERS LOG

COMPANY: MCAAM Oil Company, Inc. WELL NAME: Yost #1
 DESCRIPTION:
 CONTRACTOR: MALLARD DRILLING CO., INC. C SW $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$
 405 Century Plaza Sec. 36-17S-24W
 Wichita, Kansas 67202

RIG NO.: 1 COUNTY: Ness
 TOTAL DEPTH: 4466 ELEVATION: 2423 gr.
 COMMENCED: September 18, 1981 COMPLETED: September 26, 1981

CASING RECORD:
 8 jts. new 24# 8-5/8" surface

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, shale	0	1210	Ran 321' new 24# 8-5/8" surface casing; set and cemented with 190 sacks common cement, 2% gel, 3% CaCl at 330' with landing joint. Cement circulated. Plug down @ 2:00 a.m. September 19, 1981
Sand	1210	1413	
Shale	1413	1724	
Anhydrite	1724	1757	
Shale	1757	2520	
Shale w/sand	2520	3030	
Shale	3030	3708	
Shale and lime	3708	3880	
Lime	3880	4461	
Mississippi	4461	4466	

Hole plugged with 130 sacks 50/50 pozmix, 4% gel, 3% CaCl as follows: 70 sacks @ 960'; 40 sacks @ 300'; 10 sacks & hulls @ 40'; 5 sacks in mouse-hole and 5 sacks in rathole. Plugging completed at 12:00 p.m. September 26, 1981.

RECEIVED
 STATE CORPORATION COMMISSION

OCT 5 1981
 10-05-1981
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the YOST #1 well, to the best of my knowledge.

John Jay Darrah, Jr.
 John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 30 day of September, 1981.

Dianne R. Fowler
 Dianne R. Fowler Notary Public

My Commission Expires:
 August 25, 1984