

API NUMBER 15-135-22,373-00-00

LEASE NAME Ummel

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

4290 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 36 TWP. 17 RGE. 24 (X) or (W)

COUNTY Ness

Date Well Completed 5-6-83

Plugging Commenced 10:00 AM

Plugging Completed 12:30 PM  
9-28-94 (date)

LEASE OPERATOR Ummel's Tank Service

ADDRESS Box 37 Brownell Ks. 67521

PHONE#(913) 481-2316 OPERATORS LICENSE NO. 4011

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/28/94

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 4407 Bottom 4411 T.D. 4460

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	oil	0	4460	4 1/2	4460	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
4 1/2" casing previously squeezed at 1257' - 1st Plug set CIBP at 4300' Pressured to 400# - 2nd Plug Perforated  
4 1/2" casing & Pumped 150 SX Cement Had slight Circulation  
3rd Plug Pumped in 8 7/8" x 4 1/2" Annulus with 100 SX Cement. Pump Pressure on 4 1/2" casing 0 - 500# Start in 200 PSI  
Pumping Pressure on 8 7/8" x 4 1/2" Annulus 0 - 500# Start in 200# PSI - No casing Recovery - Used 6 5/8" 202 mix  
 (If additional description is necessary, use BACK of this form.) 6 2061

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Ness City KS


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. Dean Ummel

STATE OF Kansas COUNTY OF Ness, ss.

(Employee of Operator) \_\_\_\_\_ (Operator) \_\_\_\_\_  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

X (Signature) L. Dean Ummel  
 (Address) PO Box 37 Brownell Ks

SUBSCRIBED AND SWORN TO before me this 16<sup>th</sup> day of Nov, 19 94



X M. J. Pfannenstiel  
 Notary Public