

15-135-20690-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

NESS County, Sec. 34 Twp. 17 Rge. 24 (W)

Location as "NE/CNW/SW" or footage from lines SE SE  
Lease Owner DANE G HANSEN TRUST  
Lease Name H DEPPERSCHMIDT Well No. 1  
Office Address LOGAN, KANSAS 67646  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed OCTOBER 9 19 72  
Application for plugging filed OCTOBER 9 19 72  
Application for plugging approved OCTOBER 9 19 72  
Plugging commenced OCTOBER 9 19 72  
Plugging completed OCTOBER 9 19 72  
Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES  
Name of Conservation Agent who supervised plugging of this well LEO F MASSEY, HAYS, KANSAS

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4440 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	320.71	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILLED WITH HEAVY MUD TO 600'. SET PLUG.  
PUT IN 70 SACKS CEMENT. FILLED WITH HEAVY  
MUD TO 300'. SET PLUG. PUT IN 205 SACKS  
CEMENT. FILLED WITH HEAVY MUD TO 40'.  
PUT IN 1 SACK HULLS AND 10 SACKS CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
10-18-1972


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor C-G DRILLING CO.  
Address 1107 UNION NATIONAL BUILDING, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
G F GALLOWAY (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway 1107 Union Natl Bldg  
(Address)

Subscribed and sworn to before me this 3rd day of October, 1972.



Phyllis Buchanan  
Notary Public.

15-135-20690-00-00

W E L L L O G

OPERATOR: DANE G HANSEN TRUST

WELL NAME: H. DEPPERSCHMIDT #1 LOCATION: SE SE SEC 34-17S-24W

COUNTY: NESS STATE: KANSAS

WELL COMMENCED: 9/28/72 WELL COMPLETED: 10/9/72

ELEVATION: 2369 KB TOTAL DEPTH: 4440'

PRODUCTION: D & A RIG NO: 1

CASING - 8-5/8": Ran 15 jts, 320.71' 28# 8 5/8" Used w/200 Sxs Quickset  
60-40 2% Gel  
5-1/2": \_\_\_\_\_

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1640	SHALE & SHELLS		
1640	1669	SHALE		
1669	1705	ANHYDRITE		
1705	1925	SHALE		
1925	3805	SHALE & LIME	1 1/4° 1700'	
3805	3891	LIME	3/4° 3802'	
3891	3980	LIME & SHALE		
3980	4382	LIME		DST #1 4348'-4375'
4382	4440	MISSISSIPPI SAND		DST #2 4359'-4385'
4440		RTD	MISRUN	DST #3 4384'-4395'
				DST #4 4359'-4395'

RECEIVED  
STATE CORPORATION COMMISSION

OCT 18 1972

CONSERVATION DIVISION  
Wichita, Kansas

10-18-1972

STATE OF KANSAS )  
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway

G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 3rd day of October, 1972.

EXP. DEC. 7, 1975

Phyllis Buchanan  
PHYLLIS BUCHANAN - NOTARY PUBLIC

