

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-21,515-00-00

LEASE NAME Weeks #1

WELL NUMBER _____

SPOT LOCATION 150'W NW NE NW

SEC. 31 TWP. 17 RGE. 24w (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 11/16/85

Plugging Completed 12/2/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Palomino Petroleum

ADDRESS P.O. Box 18610, Wichita, Ks. 67218

PHONE # (316) 683-8152 OPERATORS LICENSE NO. 5161

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4412'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	244'	none
				4 1/2"	4403'	2078'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged bottom with sand to 4250' & 4 sacks cement. Shot pipe at 2715', 2420', & 2078'. Pulled 50 joints of pipe. Started plugging well with 3 hulls, & 15 gel. Gel came outside of casing. Ran tubing to 1710' & pumped 10 gel & 50 sacks cement. Pulled up to 1020' & pumped 12 gel & 70 sacks cement. Pulled up to 270' & pumped 5 gel, & 50 sacks 60/40 poz 2% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1985

RECEIVED
STATE CORPORATION COMMISSION
Notary Public

My Commission expires:



DEC 30 1985
12-30-1985

Form CP-4
Revised 01-84