

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-21,426-00-00

LEASE NAME Keilman

WELL NUMBER B-1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line
 NE NW NW

SEC. 29 TWP. 17 RGE. 24W (E) or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 3-14-88

Plugging Completed 3-24-88

LEASE OPERATOR Midwestern Supply Co., Inc.

Box 1633

ADDRESS Great Bend, Kansas 67530

PHONE # (316) 792-6605 OPERATORS LICENSE NO. 8778

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4392'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 274' | none |
| | | | | 4-1/2" | 4387' | 2071' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4175' and 4 sacks cement. Shot pipe @3003', 2663', 2071', pulled a total of 51 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, released plug and 125 cement, 60/40 pos, 6% gel Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 24th day of March, 1988
 STATE CORPORATION COMMISSION

Jane Brown
 Notary Public

My Commission Expires:



MAR 28 1988
 03-28-1988
 Form CP 4
 CONSERVATION DIVISION 86
 Wichita, Kansas