

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-22,274-00-00

LEASE NAME Weeks 1-29

WELL NUMBER \_\_\_\_\_

SPOT LOCATION SW NW SW

SEC. 29 TWP. 17S RGE. 24W (S) or (W) (W)

COUNTY Ness

Date Well Completed \_\_\_\_\_

Plugging Commenced 7/13/84

Plugging Completed 7/18/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947, Pratt, Ks. 67124

PHONE # (316) 672-7581 OPERATORS LICENSE NO. # 5087

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.O. 4555'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	370'	none
				4 1/2"	4530'	2379'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4360' & 4 sacks cement. Shot pipe at 3700', 3200', 2900', 2700', 2500', & 2379'. Pulled total of 59 joints. Plugged well with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug, & 150 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1984



Irene Hoover  
Notary Public



My Commission expires: