


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Ness County, Sec. 29 Twp. 17S Rge. 24 E/W  
Location as "NE/CNW/SW" or footage from lines  
100' SE of C NE SW  
Lease Owner Walters Drilling Company  
Lease Name Weeks Well No. 1  
Office Address 400 Insurance Building, Wichita 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole  
Date Well completed 12/13/78 19  
Application for plugging filed 12/13/78 19  
Application for plugging approved 12/13/78 19  
Plugging commenced 12/13/78 19  
Plugging completed 12/13/78 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 4425 TD  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO  | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|-----|-------|--------|------------|
|           | Surface | 0    | 325 | 8-5/8 | yes    | no         |
|           |         |      |     |       |        |            |
|           |         |      |     |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug at 600' with 70 sacks 50/50 Poz 6% gel  
Middle plug at 300' with 20 sacks 50/50 Poz 6% gel  
Top & bridge at 40' with 10 sacks 50/50 poz 6% gel  
2 sacks in rathole

Job complete at 10:30 a.m. 12/13/78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.

STATE OF Kansas COUNTY OF Kansas, ss.  
James C. Remsberg (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature)

James C. Remsberg  
200 Douglas Building, Wichita, 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of December, 1978

Mary Lou Taylor  
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



15-135-21546-00-00

DRILLERS LOG

OPERATOR: Walters Drilling Company  
 400 Insurance Building  
 Wichita, Kansas 67202

LEASE: Weeks No. 1  
 100' SE OF C NE SW Sec.29-17S-24W  
 Ness County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
 200 Douglas Building  
 Wichita, Kansas 67202

COMMENCED: 12/5/78

COMPLETED: 12/13/78

RTD: 4425'

SURFACE CSG: 8-5/8" set at 325' with 200 sx cement

0' to 330' Sand & Clay (12 1/4" Surface Hole)  
 330' to 600' Shale & Sand  
 600' to 1470' Sand & Shale  
 1470' to 1666' Shale  
 1666' to 1698' Anhydrite  
 1698' to 2005' Shale  
 2005' to 2364' Shale, Sand & Limestone Strks.  
 2364' to 2595' Shale & Lime  
 2595' to 3350' Lime & Shale  
 3350' to 3510' Lime  
 3510' to 3680' Shale & Lime  
 3680' to 3835' Lime & Shale  
 3835' to 4304' Lime  
 4304' to 4341' Lime & Shale  
 4341' to 4425' Lime  
 4425 RTD

STATE OF KANSAS  
 COUNTY OF SEDGWICK

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 28 1978  
 12-28-1978  
 CONSERVATION DIVISION  
 Wichita, Kansas

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state that the above is an accurate copy of the Weeks No. 1 log for Walters Drilling Company.

*James C. Remsberg*  
 James C. Remsberg

Subscribed and sworn to me this 26th day of December, 1978.

*Mary Lou Taylor*  
 Mary Lou Taylor, Notary

My commission expires January 17, 1981

