

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

WELL NUMBER 15-135-24141-0000

LEASE NAME Depperschmidt

WELL NUMBER 1-28

2,970 Ft. from S Section Line

510 Ft. from <sup>W</sup>E Section Line

SEC. 28 TWP. 17 RGE. 24 (E) or (W)

COUNTY Lane

Date Well Completed 7-12-01

Plugging Commenced 7-12-01

Plugging Completed 7-12-01

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

NOV 14 2001  
11-14-2001  
Conservation Division  
Wichita, Kansas

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS PO Box 47, Great Bend, KS 67530

PHONE (316) 793-5100 OPERATORS LICENSE NO. 6569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-12-01 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4,470

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	219'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each section.  
Push plug to 1,700', pump 50 sax cement on plug thru drill pipe; push plug to 1,000', pump 50 sax cement on plug thru drill pipe; push plug to 500', pump 40 sax cement on plug thru drill pipe; push plug to 230', pump 40 sax cement on plug thru drill pipe; push plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas.

Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 16th day of July, ~~2001~~ 2001



Ruth Phillips  
Notary Public

My Commission Expires: \_\_\_\_\_