

RECEIVED

15-135-21522-00-00 FORM CP-4

NOV 3 1978

STATE OF KANSAS

STATE CORPORATION COMMISSION PALOMINO

PETROLEUM WELL PLUGGING RECORD

Give All Information Completely

Make Required Affidavit

Mail or Deliver Report to

Conservation Division

State Corporation Comm.

245 North Water

Wichita, KS 67202

County. Sec. 28 Twp. 17S Rge. 24W E/W

Location as "NE/CNW 1/4 SW 1/4" or footage from lines

SE NE NE

Lease Owner Palomino and Darrah

Lease Name Depperschmidt "B" Well No. #1

Office Address 500 Insurance Building, Wichita, Kansas 67202

Character of Well (Completed as Oil, Gas or Dry Hole)

dry hole

Date Well completed October 17, 1978 19

Application for plugging filed October 17, 1978 19

Application for plugging approved October 17, 1978 19

Plugging commenced October 17, 1978 19

Plugging completed October 17, 1978 19

Reason for abandonment of well or producing formation

dry hole

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 440'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 240', hulls and 10 sacks @ 40'. Plugging completed 1:00 p.m., October 17, 1978.

RECEIVED

STATE CORPORATION COMMISSION

NOV 13 1978

11-13-1978

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.

Kenneth J. Link (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link President

Boxe 355, Great Bend, Kansas 67530

(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 1978.

Loneita Barry

Loneita Barry

Notary Public.

My commission expires 3-28-80.



RECEIVED

15-135-21522-00-00

NOV 3 1978

PALOMINO
PETROLEUM

DRILLERS LOG

#1 Depperschmidt "B"

CASING RECORD:
7 jts. new 20#
8-5/8" surface
casing

COMPANY: Palomino and Darrah
CONTRACTOR: Strata Drilling Company
COMMENCED: October 10, 1978
COMPLETED: October 17, 1978

DESCRIPTION: SE NE NE
Section 28-17S-24W
Ness County, Kansas
ELEVATION: 2386' GL

TOTAL ROTARY
DEPTH: 4407'

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Rock and shale	0	300	
Shale, sand, shale	300	1699	
Anhydrite	1699	1730	
Shale	1730	1930	
Shale, lime streaks	1930	2340	
Shale	2340	2830	
Lime and shale	2830	4335	
Lime	4335	4407	

Ran 282' new 20# 8-5/8" surface casing, set and cemented at 287' with 185 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 10:15 p.m., October 10, 1978.

Ran one drill stem test.

Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 240', hulls and 10 sacks @ 40'. Plugging completed @ 1:00 p.m., October 17, 1978.

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1978
11-13-1978
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF BARTON)


I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA-DRILLING-COMPANY

Kenneth J. Link
Kenneth J. Link, President

Sworn to and subscribed before me this 2nd day of November, 1978.

My appointment expires 3-28-80.



Loneita Barry
Loneita Barry, Notary Public