

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 31 Twp. 11 Rge. 18 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines NE SE SE

Lease Owner American Petrofina Company of Texas

Lease Name Pfeifer "B" Well No. 2

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_

Plugging commenced 11-4-66 \_\_\_\_\_ 19\_\_

Plugging completed 11-5-66 \_\_\_\_\_ 19\_\_

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3645 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	358'	None
				5-1/2"	3640'	344'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3640', sanded hole to 3600' and  
dumped 5 sacks of cement @ 3600' with dump bailer.  
Pulled 5 1/2" casing, bridged hole @ 343' and filled  
hole with 5 yards of ready-mix cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1966  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (~~OWNER OR OPERATOR~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul J. Knight

Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of November, 1966

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

*Full in  
Pfeifer #2  
Well file*

ROTARY DRILLING LOG

OPERATOR: El Dorado Refining Co.  
Pfeifer "B" #2  
NE SE SE Sec. 31-11-18W,  
Ellis County, Kansas

CONTRACTOR: Prime Drilling Company  
COMM: 8/6/57  
COMP: 8/20/57

Remarks: Set 8-5/8" surface casing  
at 358' cemented with 185 sacks  
common cement, 4 sacks C.C.

Formations:

Surface Clay	100'
Shale & Shells	850'
Sand	1070'
Red Bed & Shale	1235'
Shale & Shells	1402'
Anhydrite	1437'
Shale & Shells	1540'
Lime & Shale	1700'
Shale & Shells	1970'
Brk. Lime	1985'
Lime & Shale	2205'
Brk. Lime	2310'
Lime	2475'
Shale & Lime	3205'
Lime	3645'
Rotary Total Depth	3645'

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 13 1956  
CONSERVATION DIVISION  
Wichita, Kansas

Set 5-1/2" casing at 3640' cemented  
with 100 sacks common cement.

We certify the above log is true and  
correct to the best of our knowledge  
and belief.

PRIME DRILLING COMPANY

*R. R. McNicol*

R. R. McNicol

- ELEC. Log Tops
- Anh. 1402 (Dis-regard)
- Heeb. 3313
- Tor. 3330
- Lan. 3352 -1266
- Arb. 3636
- RTD 3642