

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ellis County, Sec. 31 Twp. 11S Rge. 18W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE

Lease ~~XXXX~~ Operator Hummon Oil Co.

Lease Name Pfeifer Well No. 21

Office Address 6409 E. 14th, Wichita, Ks. 67206

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 10-1 1969

Application for plugging filed 19

Application for plugging approved 7-13 1972

Plugging commenced 9-16 1972

Plugging completed 9-16 1972

Reason for abandonment of well or producing formation not commercial


If a producing well is abandoned, date of last production 6-15 1972

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey PBTB

Producing formation Topeka Depth to top 3115 Bottom 3118 Total Depth of Well 3200 Feet

Show depth and thickness of all water, oil and gas formations.



OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	358	none
				5 1/2	3637	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 25 sacks cement - 3200' to 3000'
- 20 sacks gel & 3 hulls - 3000' to 130'
- 50 sacks cement - 130' to 6'

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1972 10-13-72

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. E. Leith (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Leith

6409 E. 14th, Wichita, Kansas 67206
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of October, 1972

My commission expires May 1, 1974



Schular L. Verrington
Notary Public.

*Fill in
Pfeifer # 2
Well file*

ROTARY DRILLING LOG

OPERATOR: El Dorado Refining Co.
Pfeifer "B" #2 ✓
NE SE SE Sec. 91-11-18W,
Ellis County, Kansas

CONTRACTOR: Prime Drilling Company
COMP: 8/6/57
COMP: 8/20/57

Remarks: Set 8-5/8" surface casing
at 358' cemented with 185 sacks
common cement, 4 sacks C.C.

Formations:

Surface Clay	100'
Shale & Shells	850'
Sand	1070'
Red Bed & Shale	1235'
Shale & Shells	1402'
Anhydrite	1437'
Shale & Shells	1640'
Lime & Shale	1700'
Shale & Shells	1970'
Brk. Lime	1985'
Lime & Shale	2205'
Brk. Lime	2310'
Lime	2475'
Shale & Lime	3205'
Lime	3645'
Rotary Total Depth	3645'

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1972

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1966
CONSERVATION DIVISION
Wichita, Kansas

Set 5-1/2" casing at 3640' cemented
with 100 sacks common cement.

We certify the above log is true and
correct to the best of our knowledge
and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol

- ELEC. Log Tops
- Anth. 1402 (Dis-regard)
- Heeb. 3313
- Tor. 3330
- Lan. 3352 -1266
- Arb. 3636
- RTD 3642

NOTE - THIS WELL REENTERED BY Hummon Oil Co - (PFEIFER #1)
PUC set @ 3200' - & PEEF. 3115' to 3118'