

15-135-20146-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 2 Twp. 17S Rge. 24W (E) (X) (W)

Location as "NE/CNW/SW" or footage from lines SW SW
Lease Owner Beardmore Drilling Company
Lease Name Horchem 'D' Well No. 2
Office Address Suite 700 - One Twenty Building - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-26-68 19
Application for plugging filed 5-26-68 19
Application for plugging approved 5-26-68 19
Plugging commenced 5-26-68 19
Plugging completed 5-26-68 19
Reason for abandonment of well or producing formation commercial quantities of oil not found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4520 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	220'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 800' w/ 70 sx. cement (1/2 sk. hulls)
2nd plug @ 210' w/ 20 sx. cement
Top plug @ 40' w/ 10 sx. cement 50/50 pos. 6% gel.

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1968
CONSERVATION DIVISION
Wichita, Kansas
06-07-1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Walters Drilling Co.
Address 400 Insurance Building - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Robert F. Walters (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters

400 Insurance Building - Wichita, Kansas 67202 (Address)

Subscribed and sworn to before me this 4th day of June, 1968

My commission expires October 4, 1971
Juanita M. Green Notary Public.



15-135-20146-00-00

DRILLER'S LOG

COMPANY: BEARDMORE DRILLING COMPANY
 SUITE 700 - ONE TWENTY BUILDING
 WICHITA, KANSAS 67202

WELL NAME: HORCHEM 'D' #2
 SW SW SECTION 2-17S-24W
 NESS COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO. -
 400 INSURANCE BUILDING
 WICHITA, KANSAS 67202

ROTARY DRILLING COMMENCED: MAY 16, 1968
 ROTARY DRILLING COMPLETED: MAY 26, 1968

ELEVATION: 2513 KB

CASING RECORD: 8 5/8" @ 220' w/ 140 sx. cement

LOG

0 - 220	Shale and Sand
220 - 630	Shale
630 - 1170	Shale and Shells
1170 - 1180	Blaine
1180 - 1280	Shale
1280 - 1710	Shale and Shells
1710 - 1820	Shale
1820 - 1840	Anhydrite
1840 - 2150	Shale
2150 - 2675	Shale and Lime
2675 - 2825	Lime and Shale
2825 - 3200	Lime
3200 - 3725	Lime and Shale
3725 - 3840	Shale and Lime
3840 - 3960	Lime and Shale
3960 - 4467	Lime
4467 - 4488	Core
4488 - 4489	Lime
4489 - 4508	Core
4508 - 4520	Lime
<u>4520</u>	<u>Rotary Total Depth</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 7 1968
 CONSERVATION DIVISION
 Wichita, Kansas


06-07-1968

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By Robert F. Walters
 Robert F. Walters, Partner

Subscribed and sworn to before me
 this 4th day of June, 1968.



Juanita M. Green
 Juanita M. Green, Notary Public

Commission Expires: October 4, 1971