

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-24221-0000

LEASE NAME Yost-Klitzke

WELL NUMBER 1

1,400 Ft. from S Section Line

150 Ft. from E Section Line

SEC. 1 TWP. 17 RGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed 4-29-03

Plugging Commenced 4-29-03

Plugging Completed 4-29-03

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS PO Box 47, Great Bend, KS 67530

PHONE (620) 793-5100 OPERATORS LICENSE NO. 6,569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-29-03 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	219'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Push plug to 1,860', pump 50 sax cement on plug thru drill pipe; push plug to 980', pump 80 sax cement on plug thru drill pipe; push plug to 500', pump 40 sax cement on plug thru drill pipe; push plug to 230', pump 40 sax cement on plug thru drill pipe; push plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO.

License No. 5184

Address Box 709, Russell, KS 67665

RECEIVED
05-07-2003
MAY 07 2003

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CARMEN SCHMITT, INC.

KCC-WICHITA

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas.

Contractor


above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 2003

My Commission Expires: _____



Ruth Phillips
Notary Public




Shields

15-135-24221-0000
Russell, Kansas

WELL LOG

Operator: CARMEN SCHMITT, INC.
Well: Yost-Klitzke #1
Commenced: April 21, 2003
Completed: April 29, 2003
Contractor: Shields Drilling Co.

Well Description: Approx. 80' N & 65' E
of W/2 W/2 W/2 SW/4
Sec. 1-17S-24W
Ness Co., KS



CASING RECORD

Size Run Pulled
8 5/8" 219' Cmtd. w/150 sax

Elevation: 2,490' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Shale & sand	1,817'
Anhydrite	1,852'
Shale & sand	2,070'
Shale	3,888'
Shale & lime	4,117'
Lime	4,342'
Lime & shale	4,427'
Lime	4,590'
Lime & shale	4,625' RTD

RECEIVED
MAY 07 2003
KCC WICHITA
05-07-2003

Notes