

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,047-00-01

LEASE NAME Davision

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 32 TWP. 18 RGE. 24W or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 4-8-91

Plugging Completed 4-10-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Shamrock Resources, Inc.

ADDRESS 100 N. Main #802 One Main Place Bldg.

PHONE#() Wichita, Ks. 67202
OPERATORS LICENSE NO. 30075

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	234'	none
				5 1/2"	4499'	2935'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4330' dumped 5 sacks cement. Shot pipe @3221',
3016', 2935'. Spotted 65 sacks @1575', 80 sacks @925', circulated
@275' w/70 sacks topped off with 5 sacks to surface 220 sacks
65/35 8% gel.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shamrock Resources, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1991

SUBSCRIBED AND SWORN TO before me this 17 day of April, 19 91

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires:

IRENE HERZBERG
State of Kansas
My Appt. Exp. Aug. 24, 1993

Notary Public

Form CP-4
Revised 05-88



**Sonic Cement
Bond Log**

HAYS, KS Topeka, Ks.

FILING NO.	COMPANY	SHAMROCK RESOURCES	RECEIVED STATE CORPORATION COMMISSION MAR 25 1991 CONSERVATION DIVISION STATE OF KANSAS
	WELL	DAVISON NO. 1	
	FIELD		
	COUNTY	NESS	
Location		N/2-NW-SW	Other Services:
Sec.	32	Twp. 18S	Rge. 24W

Permanent Datum	GROUND LEVEL	Elev.		Elev.: K.B.
Log Measured From	KELLY BUSHING	5	Ft. Above Perm. Datum	D.F.
Drilling Measured From	KELLY BUSHING			G.L.

Run No	ONE
Date & Time Survey	FEB. 21, 1991 10:30 AM
Date & Time Cementing	////
Type Cementing Operation	PRIMARY
Depth Driller	4500
Depth Logger	4467
Logged Interval	4464 to 4000
Casing Driller	5 1/2" @ TD
Float Collar—D.V. Tool	////
Squeeze Depth	////
Amount & Type Cement	////
Amount & Type Admix	////
Type Fluid in Hole	WATER
Fluid Level	FULL
Salinity PPM Cl	////
Weight lb/gal—Vis.	////
Approx. Logged Cem. Top	4087
Calculated Cement Top	
Max. Hole Temperature	123 F.
Tool No	15
Spacing Recorded	3'
Equipment - Location	2 HAYS
Recorded by	B. DPYLIE
Witnessed by	ITX LINE

Joan Finney
Governor

Jim Robinson
Chairman

Keith R. Henley
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian J. Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

April 16, 1991

Shamrock Resources, Inc.
100 N. Main, #802
Wichita, KS 67202

Division 1
API 15-135-23,047-A
Sec. 32-18-24W
Ness County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760