


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 31 Twp. 18S Rge. (E) 24 (W)
Location as "NE/CNW&SW&" or footage from lines C/NE SE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Gantz Well No. 1
Office Address Box 18407, 4328 East Kellogg, Wichita, Kansas 67218
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 9 19 74
Application for plugging filed June 9 19 74
Application for plugging approved June 9 19 74
Plugging commenced June 9 19 74
Plugging completed June 9 19 74
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	329'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: Plugged at 650' with 70 sacks of 50-50 pozmix and 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix and 6% gel; plugged at 40' with 20 sacks of 50-50 pozmix and 6% gel. Plug down at 1:00 P. M. June 9, 1974.

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling Company
Address P. O. Box 355, Great Bend, Kansas 67530


STATE OF KANSAS COUNTY OF BARTON ss.
Kenneth J. Link (Signature) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link
Kenneth J. Link
P. O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 10th day of June, 19 74

My commission expires December 14, 1977

Elaine H. Taylor
Elaine H. Taylor Notary Public.



D R I L L E R S L O G

#1 Gantz

CASING RECORD:
324.41' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C/NE SE
Section 31-18S-24W
Ness County, Kansas

TOTAL DEPTH:
4480'

COMMENCED: May 30, 1974
COMPLETED: June 9, 1974

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay	0	20	Ran 324.41' of used 8-5/8" surface casing; set and cemented at 329' with 200 sacks of common cement, 2% gel and 3% C. C. Plug down at 2:15 A. M. May 31, 1974.
Shale	20	302	
Shale, Clay w/Sand Streaks	302	350	
Shale & Red Bed	350	995	
Anhydrite	995	1007	
Shale & Red Bed	1007	1030	
Sand & Shale	1030	1655	
Shale	1655	1980	
Shale & Shells	1980	2300	
Shale & Lime	2300	4389	
Lime	4389	4480	

ROTARY TOTAL DEPTH: 4480'

Ran electric log.

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1974
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Hole plugged as follows: Plugged at 650' with 70 sacks of 50-50 pozmix and 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix and 6% gel; plugged at 40' with 20 sacks of 50-50 pozmix and 6% gel. Plug down at 1:00 P. M. June 9, 1974.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link

Subscribed and sworn to before me this 10th day of June, 1974.

My Commission Expires:

December 14, 1974

Elaine H. Taylor
Elaine H. Taylor, Notary Public

