

15-135-20173-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ness County. Sec. 31 Twp. 18 Rge. 24W ~~XK~~ (W)  
Location as "NE/CNW/SW" or footage from lines C SW SW  
Lease Owner Tilco & McClure  
Lease Name Miner A-1 Well No. \_\_\_\_\_  
Office Address 815 Wichita Plaza Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 8-16-68 1968  
Application for plugging filed 8-16-68 1968  
Application for plugging approved 8-16-68 1968  
Plugging commenced 8-16-68 1968  
Plugging completed 8-16-68 1968  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Pfannenstiel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4460 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	402.49	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 70 sacks 50/50 Posmix 6% Gel @ 660 Spotted 20 sacks 50/50 Posmix 6% Gel @ 390 Bridged @ 40' with 1/2 Hulls

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address)

SUBSCRIBED AND SWORN to before me this 26th day of August, 1968.

My commission expires April 1, 1971

Ulanda Nichols  
Notary Public.

DRILLER'S LOG

COMPANY	Tilco & McClure
CONTRACTOR	Leben Drilling, Inc.
FARM	Miner A-1
LOCATION	C SW SW Section 31-18S-24W
COMMENCED	Ness County, Kansas
COMPLETED	8-6-68
	8-16-68

0	60	Damn Hard
60	170	Clay, Sand
170	220	Blue Shale
220	410	Shale, Shells
410	1040	Shale, Sand
1040	1160	Red Bed, Shale
1160	1565	Shale, Shells
1565	1662	Shale, Red Bed
1662	1702	Anhydrite
1702	1980	Shale, Shells
1980	2343	Shale, Lime
2343	2585	Lime, Shale
2585	2885	Lime
2885	3045	Lime, Chalk
3045	3260	Shale, Lime
3260	3600	Lime, Shale
3600	3780	Shale, Lime
3780	3960	Lime, Shale
3960	4460	Lime
	4460	Set @ 5½

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Run 8 5/8" casing ran 10 Jts. New 20# casing overall 402.49 set @ 210 Cement with 275 sacks Common 2% c.c.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Miner A-1 Well, located C SW SW of Section 31, Township 18 South, Range 24 West, Ness County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*  
Leslie Kite

STATE OF KANSAS            SS  
COUNTY OF BARTON

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 26th day of August, 1968.



*Ulanda Nichols*  
Ulanda Nichols

My Commission Expires:  
April 1, 1971