

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 30 Twp. 18S Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines c SE SE

Lease Owner Hellar Drilling Company, Inc.

Lease Name Bondurant Well No. 1

Office Address 1014 Union Center, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 19, 1963

Application for plugging filed February 19, 1963

Application for plugging approved February 19, 1963

Plugging commenced February 19, 1963

Plugging completed February 19, 1963

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty, Box 326, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	288'	8 5/8"	288'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Set Plug @ 500' 20 sacks cement
- Plug @ 240' 20 sacks cement
- Plug @ 40' 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

MAR 1 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.

Address 1014 Union Center, Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.


D. L. Hellar, Pres. of Hellar Drlg. Co. Inc (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar D. L. Hellar, Pres.  
1014 Union Center, Wichita 2, Kansas

SUBSCRIBED AND SWORN TO before me this 27th day of February, 1963

My commission expires March 25, 1964

Catherine Darcey  
Catherine Darcey -- Notary Public.



DRILLER'S LOG

COMPANY: Hellar Drilling Company, Inc.  
 CONTRACTOR: Hellar Drilling Company, Inc.  
 LEASE: #1 Bondurant  
 LOCATION: c SE SE Section 30-18S-24W  
 Ness County, Kansas  
 COMMENCED: February 8, 1963  
 COMPLETED: February 19, 1963  
 CASING: Set 8 5/8" surface casing @ 288'/200 sacks cement

0- 273	Sand, clay, sand
273 - 305	Shale
305- 988	Shale & Red Bed
988-1005	Blaine Anhydrite
1005-1395	Sand, shale & Red Bed
1395-1637	Shale & Shell & Red Bed
1637-1658	Anhydrite
1658-1925	Shale - Shells
1925-2229	Salt Section
2229-2340	Shale-Lime
2340-2374	Ft. Riley
2374-2862	Lime & Shale
2862-3040	Shale & Lime
3040-3185	Shale & Lime chalky
3185-3648	Shale & Lime
3648-3800	Lime & Shale
3800-3858	Lansing-Kansas City
3858-3960	Lime
3960-4007	Lansing-Kansas City
4007-4242	Lime
4242-4375	Lime & Shale
4375-4390	Lime & chert
4390-4396	Lime
4396-4410	Mississippi
4410-4437	Dolomite
4437-4455	Mississippi
4455	Rotary Total Depth
	Dry & Abandoned

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 1 1963

CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Bondurant, located in c SE SE Section 30-18S-24W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*  
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 27th day of February, 1963.

My Commission Expires:  
 March 25, 1964.

*Catherine Darcey*  
 Notary Public - Catherine Darcey