


15-135-21269-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ness County, Sec. 19 Twp. 17S Rge. (E) 24 (W)
Location as "NE/CNWxSWx" or footage from lines C SE NE
Lease Owner Palomino Petroleum
Lease Name Schaben Well No. 1
Office Address 304 Insurance Bldg. Wichita, Kansas ; 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 25 19 76
Application for plugging filed November 25 19 76
Application for plugging approved November 25 19 76
Plugging commenced November 25 19 76
Plugging completed November 25 19 76
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas 67601
Producing formation Depth to top Bottom Total Depth of Well 4415 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	287'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: - Plugged at 720' with 70 sacks of 50-50 Pozmix and 6% gel; plugged at 240' with 20 sacks of 50-50 Pozmix and 6% gel; plugged at 40' with 10 sacks 50-50 Pozmix and 6% gel. Plug down at 12:15 P.M., November 25, 1976

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1976

CONSERVATION DIVISION
Wichita, Kansas

12-21-1976

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company
Address P.O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.


Kenneth J. Link (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link
Kenneth J. Link, President
P.O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and Sworn to before me this 3rd day of December, 19 76

Joy Selves
Notary Public.

My commission expires November 30, 1979



D R I L L E R S L O G

#1 Schaben

CASING RECORD:	COMPANY:	Palomino Petroleum	DESCRIPTION: C SE NE
287' of new 8-5/8" surface casing	CONTRACTOR:	Strata Drilling Company	Section 19-17S-24W
	COMMENCED:	November 17, 1976	Ness County, Kansas
	COMPLETED:	November 25, 1976	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	305	Ran 282.46' of new 8-5/8" 20 lb. surface casing; set and cemented at 287' with 175 sacks of common cement, 2% gel, 3% C.C. Plug down at 12:30 A.M. September 17, 1976. Cement circulated.
Shale	305	825	
Shale and Sand	825	1663	
Anhydrite	1663	1691	
Shale & Sand	1691	2390	
Lime and Shale	2390	4340	
Lime and Sand	4340	4355	
Lime and Shale	4355	4370	
Lime	4370	4415	
			Ran electric log.

ROTARY TOTAL DEPTH: 4415

D. & A.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1976
18-21-1976
CONSERVATION DIVISION
Wichita, Kansas

Plugged hole as follows: Plugged at 720' with 70 sacks of 50-50 Pozmix and 6% gel; plugged at 240' with 20 sacks of 50-50 Pozmix and 6% gel; plugged at 40' with 10 sacks of 50-50 Pozmix and 6% gel. Plug down at 12:15 P.M. November 25, 1976.

STATE OF KANSAS)
)
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Subscribed and sworn to before me this 3rd day of December, 1976.

My Appointment Expires:

November 30, 1979

Joy Selves
Joy Selves, Notary Public

