

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-135-21171-00-00

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit:
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ness County, Sec. 19 Twp. 17S Rge. (E) 24 (W)
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner Martin Explorations
Lease Name Schaben Well No. 1
Office Address 527 Union Center Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 14 19 76
Application for plugging filed March 14 19 76
Application for plugging approved March 14 19 76
Plugging commenced March 14 19 76
Plugging completed March 14 19 76
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	285'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: Plugged at 720' with 70 sacks of 50-50 pozmix & 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix and 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix and 6% gel. Plug down at 3:15 P. M. March 14, 1976.

RECORDED
MAR 24 1976
03-24-1976
Conservation Division
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling Company
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Kenneth J. Link (employee of contractor) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link
Kenneth J. Link, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of March, 1976

My commission expires December 14, 1977



Elaine H. Taylor
Notary Public.

D R I L L E R S L O G

#1 Schaben

CASING RECORD:
279.44' of used 8-5/8"
surface casing.

COMPANY: Martin Explorations
CONTRACTOR: Strata Drilling Company
COMMENCED: March 6, 1976
COMPLETED: March 14, 1976

DESCRIPTION: SW NW NW
SECTION 19-17S-24W
Ness County, Kansas
ELEVATION: 2376' GL

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>	
Shale & Sand	0	130	Ran 279.44' of used surface casing; set and cemented at 285' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 8:30 P. M. March 6, 1976.	
Shale	130	300		
Shale w/Sand Streaks	300	1750		
Shale & Lime	1750	3005		
Lime	3005	3165		
Lime & Shale	3165	4055		
Lime	4055	4145		
Lime & Shale	4145	4215		
Lime	4215	4254		
Lime & Shale	4254	4315		
Sand & Lime	4315	4330		Ran three drill stem tests.
Sand	4330	4370		

ROTARY TOTAL DEPTH: 4370'

D. & A.

Hole plugged as follows: Plugged at 720' with 70 sacks of 50-50 pozmix and 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix and 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix and 6% gel. Plug down at 3:15 P. M. March 14, 1976.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.


STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Subscribed and sworn to before me this 16th day of March, 1976

My Commission Expires:
December 14, 1987

Elaine H. Taylor
Elaine H. Taylor, Notary Public



RECEIVED
STATE NOTARIAL COMMISSION
MAR 24 1976
03-24-1976
COMMUNICATION DIVISION
Wichita, Kansas