

1 070289

~~01-21-1987~~
JAN 21 1987

API NUMBER 15-135-23,092 -0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NE, SEC. 5, T 17 S, R 24 W/E
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5190

Lease Name Lancer Well # 1

Operator: Sabre Exploration, Inc.

County Ness 145.05

Name & Address 127 East Second

Well Total Depth 4463 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Republic Drilling, Inc. License Number 9943

Address 310 West Central, #214, Wichita, KS 67202

Company to plug at: Hour: 8 p.m. Day: 21 Month: 1 Year: 19 87

Plugging proposal received from Steve Lough

(company name) Republic Drilling, Inc. (phone) 316-264-0079

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2454'
Anhydrite 1800-35'

1st plug at 1890' with 50 sx cement, 2nd plug at 1000' with 70 sx cement,

3rd plug at 270' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement:

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 p.m. Day: 21 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1835' with 50 sx cement,

2nd plug at 1000' with 70 sx cement,

3rd plug at 290' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1987
01-23-1987
CONSERVATION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 1-23-87

Signed Dan Gordon
(TECHNICIAN)

INV. NO. 16006

MAR 27 1987

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date January 9, 1987 month day year 324

API Number 15- 135-23,092-0000 2

OPERATOR: License # 5190 Name Sabre Exploration, Inc. Address 127 East Second City/State/Zip Wichita, Kansas 67202 Contact Person Matthew Totten Phone (316) 264-2635

NE SW NE Sec. 5 Twp. 17S S, Rg. 24W 3630 1650

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 9943 Name Republic Drilling, Inc. City/State Wichita, Kansas

Nearest lease or unit boundary line 990 feet County Ness

Lease Name Lancer Well # 1 Ground surface elevation 2454 feet MSL

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

Depth to bottom of fresh water 150' Depth to bottom of usable water 1250' 950'

Surface pipe by Alternate: 1 (2) Surface pipe planned to be set 240'

Conductor pipe required Projected Total Depth 4600' feet

Formation Mississippian

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 1-6-87 Signature of Operator or Agent Title

For KCC Use: Conductor Pipe Required 240 feet; Minimum Surface Pipe Required 1-6-87 feet per Alt. This Authorization Expires 7-6-87 Approved By

SPUD - 1-10-87

Sec. Twp. S, Rg. East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1890 feet depth with 50 sxs of 60/40 pozmix (6% gel)
2nd plug @ 1300-1000 feet depth with 70 sxs of 60/40 pozmix (6% gel)
3rd plug @ 270 feet depth with 40 sxs of 60/40 pozmix (6% gel)
4th plug @ 40 feet depth with 10 sxs of 60/40 pozmix (6% gel)
5th plug @ feet depth with sxs of
(2) Rathole with 15 sxs

PUSHER Steel loops TD 4463 FORMATION Miss SURFACE PIPE 8 5/8 @ 265 ANHYDRITE 1800/25 ELEVATION 2454 STARTING TIME & DATE 8:00pm COMPLETION TIME & DATE 10:30pm 1st PLUG @ 1895 FT. W/ 50 SX 2nd PLUG @ 1000 FT. W/ 70 SX 3rd PLUG @ 270 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 18 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Halliburton

TECHNICIAN Dan Gardner 60/40 6% RECEIVED STATE CORPORATION COMMISSION JAN 23 1987 01-23-1987 CONSERVATION DIVISION Wichita, Kansas