

To: 1 060053  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

9-3

API NUMBER 15- 135-20,172-00-00  
150' W of  
C SE NW, SEC. 2, T 17 S, R 24 W/X  
3300 feet from S section line  
3450 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8759

Lease Name Horchem Well # 3

Operator: Mack Energy Co.

County Ness 147.55

Name & Address P.O. Box 400

Well Total Depth 4540 feet

Duncan, OK 73534

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well  Gas Well  Input Well  SWD Well

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number

Address P.O. Box 467, Chase, KS 67524-0209

Company to plug at: Hour: 9 a.m. Day: 3 Month: 9 Year: 1997

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 4 1/2" at 4535' w/150 sx cement, Perfs at 4476-81'

1st plug at 1900' with 50 sx cement, 2nd plug at 950' with 80 sx cement,

3rd plug at 340' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug perforate casing at 950'. Circulate down 4 1/2" and back up 8 5/8", filling both strings

with cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:30 a.m. Day: 3 Month: 9 Year: 1997

ACTUAL PLUGGING REPORT 1st plug ran 1000' of tubing, pumped 50 lbs. hulls, 80 sx cement with

100 lbs. hulls. Got circulation for a short time, then lost it. Pulled tubing.

2nd plug pumped 120 sx cement with 200 lbs. hulls. Pumping pressure 500 psi, shut in with 250#.

3rd plug went down backside with 10 sx cement--locked up with 500#.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 9-8-97

Signed Michael Mauer (TECHNICIAN)

INV. NO. 48933

RECEIVED  
KANSAS  
CORPORATION  
SEP 11 1997

09-15-1997