

To: 1 071086  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-20

API NUMBER 15- 135-22,624-0000 160R  
SW SW SE, SEC. 2, T. 17 S, R. 24 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767  
Operator: Ritchie Exploration, Inc.  
Name  
Address 125 N. Market, Suite 100  
Wichita, KS 67202

330 feet from S section line  
2310 feet from E section line  
Lease Name Klitzke "P" Well # 1  
County Ness 147.06  
Well Total Depth 4525 feet

Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address: P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 p.m. Day: 20 Month: 8 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 4524' w/75 sx cement, PRTD 4502', Perfs at 4481-85'

1st plug sand back to 4425' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1500',

3rd plug pump 80 sx cement at 1000',

4th plug pump 50 sx cement at 330', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by \_\_\_\_\_ Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 20 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4420' and dump 4 sx cement on top of sand through bailer,

2nd plug pumped through casing at 1500' with 50 sx cement, stuck pipe, shot pipe at 1200' and started to work pipe. Pipe parted at 440',

3rd plug pulled pipe and pumped down 8 5/8" with 140 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
08-25-1992  
AUG 25 1992

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1440' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form)

**INVOICED**

I (did / ~~did not~~) observe this plugging.

DATE 8-27-92

Signed Dan Anderson  
(TECHNICIAN)

INV. NO. 36060