

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24221-00-00
Spot: W2W2W2SW Sec/Twnshp/Rge: 1-17S-24W
1400 feet from S Section Line, 100 feet from E Section Line
Lease/Unit Name: YOST-KLITZKE Well Number: 1
County: NESS Total Vertical Depth: 4625 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

Surface Casing Size: 8.625 feet: 219

\$150.31

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/29/2003 2:15 PM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT BERRY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: 1ST PLUG AT 1860' WITH 50 SX CMT. 2ND PLUG AT 980' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 230' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/29/2003 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:


1ST PLUG AT 1860' WITH 50 SX CMT. 2ND PLUG AT 980' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 230' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
05-13-2003
MAY 13 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED

DATE 5-14-03

INV. NO. 2003061532

Form CP-23