

1 120797

5-25

API NUMBER 15- 135-23,754-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW SE, SEC. 1, T 17 S, R 24 W/MEX

990 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6569

Lease Name Yost Well # 1

Operator: Carmen Schmitt, Inc.

County Ness

Name & Address P.O. Box 47

Well Total Depth 4590 149.17 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 8:15 p.m. Day: 25 Month: 5 Year: 19 93

Plugging proposal received from Casey Biggs

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1852'

1st plug at 1860' with 50 sx cement, 2nd plug at 950' with 80 sx cement,

3rd plug at 475' with 50 sx cement, 4th plug at 230' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11 p.m. Day: 25 Month: 5 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug at 1860' with 50 sx cement,

2nd plug at 950' with 80 sx cement,

3rd plug at 475' with 50 sx cement,

4th plug at 230' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

RECEIVED STATE CORPORATION COMMISSION

If additional description is necessary, use BACK of this form.

DATE: 6-8-93 / did not observe this plugging.

INVOICED 37856

Signed [Signature] (TECHNICIAN)

JUN 4 1993 06-04-1993 CONSERVATION DIVISION Wichita, Kansas

5-25

FOR KCC USE:

EFFECTIVE DATE: 5-19-93
DISTRICT # _____
TRAT? Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 135-23, 54-00-00 ALL BLANKS MUST BE FILLED

FORM 6-1 7/91
FORM MUST BE TYPED
FORM MUST BE SIGNED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date May 15, 1993
month day year

Spot NE SW SE Sec 1 Twp 17 S Rg 24 East West

OPERATOR: License # 6569
Name: CARMEN SCHMITT, INC.
Address: P.O. Box 47
City/State/Zip: Great Bend, Kansas 67530
Contact Person: Carmen Schmitt
Phone: 316/793-5100

990 feet from South /Marsh line of Section
1650 feet from East /MEEK line of section
IS SECTION REGULAR IRREGULAR?

CONTRACTOR: License # 5929
Name: DUKE DRILLING CO., INC.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Ness
Lease Name: Yost Well #: 1
Field Name: Unknown

Is this a Prorated/Spaced Field? ... yes no
Target Formation(s): Miss
Nearest lease or unit boundary: 990'
Ground Surface Elevation: 2491' feet MSL
Water well within one-quarter mile: ... yes no
Public water supply well within one mile: ... yes no
Depth to bottom of fresh water: 150'
Depth to bottom of usable water: 900'
Surface Pipe by Alternate: ... 1 2
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: N/A
Projected Total Depth: 4550
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well farm pond other

DNR Permit #: _____
Will Cores Be Taken?: ... yes no
If yes, proposed zone: **RECEIVED**

Well Drilled For: Well Class: Type Equipment:
 Oil ... Erk Res Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OVMG ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other

If OWMG, old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, true vertical depth: _____
Bottom Hole Location: _____

KANSAS CORPORATION COMMISSION
200' Alt. II Req.

Exp. 11/14/93

AFFIDAVIT

Pusher Cally B. 995
SPUD DATE 5-17 INIT. SJD
LENGTH SURFACE PLANNED 200'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLE AHEAD? Y N SIZE HOLE _____
SURFACE PIPE 850' @ 210 CONDUCTOR _____
ANHYDRITE T- B-1852 ELEVATION _____
TD 4590 FORMATION _____
RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
_____ SX _____ Y _____ N _____
Arbuckle Plug @ _____ Ft. W/ _____ SX
Hug./Council @ _____ Ft. W/ _____ SX
Anhydrite Base @ 1860 Ft. W/ 50 SX
1/2 Base Anyh. @ 950 Ft. W/ 80 SX
1/2, 1/2 Plug @ 475 Ft. W/ 50 SX
Bottom Surface @ 230 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/10 SX

WATER WELL _____ SX (Irr. Well _____ Pond _____)
Hauling _____
TECHNICIAN SM DATE 5-24
TYPE OF CEMENT 60/40 6% 1/4 Floseed
STARTING TIME 8:15 (AM/PM) DATE 5-25-93
COMPLETION TIME 11:00 (AM/PM) DATE 5-25-93
RECEIVED
KANSAS CORPORATION COMMISSION
06-04 1993