

4-10

237

To: 1 070937
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,047-~~1~~-00-01

N/2 NW SW, SEC. 32, T. 18, S. R. 24 W/4

2310 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30075

Operator: Shamrock Resources, Inc.

Name & Address 100 N. Main, Ste. 802

Wichita, KS 67202

Lease Name Davison Well # 1

County Ness 146.25

Well Total Depth 4500 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 234

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 10 Month: 4 Year: 19 91

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4499', PBTD 4400', Perfs at 4385-89, 4404-13'

1st plug sand back to 4330' and dump 5 sx cement on top of sand through bailer,

2nd plug pull casing to 1575' and pump 65 sx cement,

3rd plug pull to 925' and pump 80 sx cement, 4th plug pull to 275' and circulate with 70

sx cement, 5th plug pull all casing and top off with 5 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:05 p.m. Day: 10 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 5 sx cement on top of sand through bailer,

2nd plug pulled casing to 1575' and pumped 65 sx cement,

3rd plug pulled to 925' and pumped 80 sx cement,

4th plug pulled to 275' and circulated with 70 sx cement,

5th plug pulled all casing and topped off with 5 sx cement.

Remarks: Used 65/35 Pozmix 8% gel 1/4# floseal by Allied. Recovered 2911' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-22-91

INV. NO. 31643

observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

APR 16 1991

CONSERVATION DIVISION Wichita, Kansas