

1 120055

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,884-0000

C SE NE, SEC. 29, T 18 S, R 24 W/E

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Stoecklein Well # 1

Operator: Energy Three, Inc.

County Ness 142.19

Name & Address P. O. Box 1505

Well Total Depth 4375 Mississippi feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 554

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Big Three Drilling, Inc. License Number 5836

Address Box 52, Gorham, KS 67640

Company to plug at: Hour: 5:00 pm Day: 23 Month: September Year: 1985

Plugging proposal received from Stan Lovelady

(company name) Big Three (phone) 913-637-5487

Elevation 2305'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1574-1615'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 60 sx cement

3rd plug 50' out of the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with
10 sx cement Plugging Proposal Received by Don C. Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:45 pm Day: 23 Month: September Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1605' with 50 sx cement, 2nd plug at 800' with

60 sx cement, 3rd plug at 594' with 50 sx cement, 4th & 5th plugs - solid bridge- hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE OCT 03 1985

SEP 27 1985

Signed Don C. Ubel (TECHNICIAN)

INV. NO. 10318